

Impatiens tainingensis (Balsaminaceae), a new species from southeastern China

Meizhen Wang^{1,2*}, Jiedong Lin^{3*}, Boheng Li⁴, Junlong Li⁵, Xinjie Jin⁶, Pan Li^{7,8}

¹ Keqiao Science and Technology Innovation Center, Zhejiang Shuren University, Shaoxing 312028, China

² College of Biology and Environmental Engineering, Zhejiang Shuren University, Hangzhou 310015, China

³ Educational Technology Center of Fujian Province, Fuzhou 350003, China

⁴ YOUNG NATURALIST (Hangzhou) Cultural Communication Co. Ltd., Hangzhou 310058, China

⁵ College of Life Science, Zhejiang Sci-Tech University, Hangzhou 330104, China

⁶ College of Life and Environmental Science, Wenzhou University, Wenzhou 325035, China

⁷ Key Laboratory of Biodiversity and Environment on the Qinghai-Tibetan Plateau, Ministry of Education, School of Ecology and Environment, Xizang University, Lhasa 850000, China

⁸ Motuo Biodiversity Observation and Research Station of Xizang Autonomous Region, Motuo 860700, China

Corresponding authors: Pan Li (panli@zju.edu.cn); Xinjie Jin (xinjie_jin@yeah.net)

Abstract

Impatiens tainingensis J.-D.Lin & P.Li, **sp. nov.**, is described and illustrated. It was collected from a moist valley of Mt. Zhuangyuanyan, Fujian Province, in Southeastern China. It resembles *Impatiens platysepala* Y.L. Chen, *I. kuocangshanica* (X.F. Jin & F.G. Zhang) X.F. Jin & Y.L. Xu and *I. huangyanensis* subsp. *attenuata* X.F. Jin & Z.H. Chen in the gross morphology of their pinkish purple flowers but differs in having smaller lateral sepals, subsaccate-funnel form lower sepals, shorter spurs, and capsules. The molecular phylogeny of *Impatiens* based on plastome and ITS sequences indicated that *I. tainingensis* is closely related to *I. platysepala* and *I. wuyiensis* J.S. Wang, Y.F. Lu & X.F. Jin, but morphology, phylogeny, and plastome structural variation comparison provide evidence for recognizing it as a distinct species.

Key words: Balsaminaceae, *Impatiens kuocangshanica*, *I. tainingensis*, *I. wuyiensis*, new species



Academic editor: Michael Pirie

Received: 25 September 2025

Accepted: 19 December 2025

Published: 19 January 2026

Citation: Wang M, Lin J, Li B, Li J, Jin X, Li P (2026) *Impatiens tainingensis* (Balsaminaceae), a new species from southeastern China. PhytoKeys 269: 235–252. <https://doi.org/10.3897/phytokeys.269.173115>

Copyright: © Meizhen Wang et al.
This is an open access article distributed under terms of the Creative Commons Attribution License (Attribution 4.0 International – CC BY 4.0).

Introduction

The family Balsaminaceae consists of two genera, *Hydrocera* Blume ex Wight & Arn. (1834: 140) and *Impatiens* L. (1753: 937). *Hydrocera* is monotypic and contains only the aquatic *H. triflora* (L.) Wight & Arn. (1834: 140), while *Impatiens* has over 1000 species worldwide, mostly distributed in paleotropical and subtropical mountainous regions. As one of the five hotspots for *Impatiens*, China is home to about 352 species, of which 273 are endemic (Yu 2012; Yuan et al. 2022). The mountainous regions in southwestern China, particularly in Yunnan, Sichuan, and Xizang provinces, harbor more than 300 species (Chen et al. 2007; Chen et al. 2023). *Impatiens* is well known for its high level of endemism, with many species

* These authors contributed equally.

confined to very narrow ranges. This pattern is especially pronounced in the karst (limestone) regions of Yunnan, Sichuan, Guizhou, and Guangxi (Chen et al. 2007).

Compared to the species-rich southwestern region of *Impatiens*, fewer species are distributed in the eastern and southern regions (Anhui, Zhejiang, Jiangxi, Fujian, and Guangdong provinces). Nevertheless, the mountainous areas along the Pacific coast in southeastern China, especially the regions associated with the Wuyi Mountain range in Fujian, Jiangxi, and Zhejiang provinces, may represent a secondary diversification center for *Impatiens*. Within this region, Jiangxi hosts 25 species of *Impatiens*, Zhejiang 21 species (six of which are provincial endemics), and Fujian 12 species (including one provincial endemic) (Chen et al. 2023). In addition, 15 taxa have been described in recent years (Chen 1988; Chen 1989; Chen and Xu 1993; Chen 1999; Xu and Chen 1999; Jin and Ding 2002; Jin et al. 2008). It is intriguing that 10 new species were based on plants from Zhejiang. Additional new species might be discovered if extensive botanical investigations are carried out in similar areas with complex topography and rich biodiversity in eastern China, such as Jiangxi and Fujian provinces.

During a survey in Fujian Province, we found a population of *Impatiens* in a valley of Mt. Zhuangyuanyan, Taining County. It appeared to be similar to *I. platysepala* (1993: 6) and *I. kuocangshanica* (2017: 34) in the gross morphology of their pinkish purple flowers, but differed in having smaller lateral sepals, a subsaccate, funnel-formed lower sepal, and shorter spurs and capsules. Molecular phylogeny indicates that it is closely related to *I. platysepala* and *I. wuyiensis* (2020: 3), further confirming the distinct nature of this putative new species. We therefore recognize it as a new species, *Impatiens tainingensis* J.-D.Lin & P.Li, sp. nov., and describe and illustrate it here.

Materials and methods

Sampling and morphology

We sampled this new species in Taining County, Fujian Province, China (Fig. 1). Morphological characters were observed and measured based on living plants and specimens. Herbarium specimens from AU, BJFC, CSH, CSFI, HHBG, HTC, HZU, IBSC, KUN, LBG, PE, and ZM (acronyms according to Index Herbariorum, <https://sweetgum.nybg.org/science/ih/>) were examined for morphological comparison. Voucher specimens were deposited at the Herbarium of Zhejiang University (HZU; acronyms according to Index Herbariorum, <https://sweetgum.nybg.org/science/ih/>).

DNA sequencing and phylogenetic analyses

Total genomic DNA was extracted from silica gel-dried leaves using Plant DNAzol (Shanghai, China), following the manufacturer's protocol. Sequencing libraries were prepared at China National GenBank (CNGB, Shenzhen, China), and paired-end reads of 150 bp were generated on the Illumina HiSeq X10 platform. To determine the phylogenetic relationships of *Impatiens tainingensis*, we retrieved 152 sequences of nuclear ribosomal internal transcribed spacer (ITS), 120 sequences of *atpB-rbcL*, and 70 sequences of *trnL-F* plastid regions

from previous *Impatiens* studies (Suppl. material 1; Yu et al. 2016). In addition, 58 complete plastome sequences of *Impatiens* were downloaded from NCBI, and six individuals (two of *I. tainingensis* and one each of *I. huangyanensis* subsp. *attenuata*, *I. kuocangshanica*, *I. wuyiensis*, and *I. platysepala* var. *chloroxantha* (2017: 34)) were newly sequenced and deposited in GenBank (Suppl. materials 1, 2). Complete plastome and ITS sequences were assembled using GetOrganelle (Jin et al. 2020) with default settings and aligned using MAFFT v7.487 (Kato and Standley 2013). Maximum likelihood (ML) analyses were performed in IQ-TREE 2 (Minh et al. 2020) with 1000 bootstrap replicates and ModelFinder (Kalyaanamoorthy et al. 2017) for gene partitioning and selection of the best-fit models. Bayesian inference (BI) analyses were conducted in MrBayes v3.2.7a (Ronquist et al. 2012). The Markov chain Monte Carlo (MCMC) algorithm was run with two independent chains and default priors for 10,000,000 generations, with trees sampled every 1000 generations. *Hydrocera triflora* was used as the outgroup. The final tree was visualized and exported using FigTree v1.4.4 (<http://tree.bio.ed.ac.uk/software/figtree/>).

IR/SC boundary comparison

The boundaries of the four plastid regions are LSC/IRb, IRb/SSC, SSC/IRa, and IRa/LSC. The phenomenon of IR region contraction and expansion during plastid evolution in *Impatiens* were analyzed through IR/SC boundary comparisons. The distribution of plastid genes at each boundary was examined using IRscope (<https://irscope.shinyapps.io/irapp/>, Amiryousefi et al. 2018).



Figure 1. Distribution map of *Impatiens tainingensis*.

Results

Morphological comparison

Detailed morphological comparisons between the new species and three similar *Impatiens* species are summarized in Table 1. *Impatiens tainingensis* (Figs 2, 3) resembles *I. platysepala*, *I. kuocangshanica*, and *I. huangyanensis* subsp. *attenuata* in the gross morphology of their pinkish purple flowers but can be distinguished by a combination of leaf and floral characters (Fig. 4). Its leaves are ovate-elliptic with 5–7 pairs of lateral veins, whereas *I. platysepala* has ovate-lanceolate leaves with 9–11 pairs of veins; leaves of *I. kuocangshanica* are similar in size and form to those of *I. tainingensis* but bear stipitate glands (absent in *I. tainingensis*); and *I. huangyanensis* subsp. *attenuata* has generally smaller leaves on shorter petioles, although the variation overlaps. In floral morphology, *I. tainingensis* is characterized by small green bracts (larger in *I. platysepala*, *I. kuocangshanica*, and *I. huangyanensis* subsp. *attenuata*; pink in *I. platysepala*), suborbicular lateral sepals (broader in *I. platysepala*), and a subsaccate-funnel-formed lower sepal (broadly funnel-formed in *I. kuocangshanica*; widely saccate in *I. huangyanensis* subsp. *attenuata*) with a shorter spur (1.5–1.8 cm; 3–4 cm long in *I. platysepala*, *I. kuocangshanica*, and *I. huangyanensis* subsp. *attenuata*).

Phylogenetic relationship

The phylogenetic results based on the same dataset inferred using maximum likelihood (ML) and Bayesian inference (BI) methods were consistent for the clade of *Impatiens tainingensis* and related species. Phylogenetic trees based on plastid and internal transcribed spacer (ITS) sequences show a close relationship among *I. tainingensis*, *I. wuyiensis*, and *I. platysepala* (Figs 5–8). The bootstrap support (BS) values and posterior probabilities (PP) for clades including *I. tainingensis* and related species based on *atpB–rbcL* and *trnL–F* sequences were relatively lower than those of the other two datasets (Figs 5, 6). Although *I. tainingensis* was strongly supported as monophyletic, interspecific relationships among closely related taxa remained unresolved, resulting in a comb-like topology in the BI trees (Figs 5, 6). These results are nevertheless largely consistent with phylogenetic relationships inferred from analyses of the complete plastid genome and the ITS dataset. Based on the complete plastid genome, *I. tainingensis* clustered with *I. platysepala*, *I. wuyiensis*, and *I. kuocangshanica* as a highly supported clade (BS = 100, PP = 0.85) (Fig. 7). Based on the ITS sequence, *I. tainingensis* clustered with *I. platysepala* var. *chloroxantha* and *I. wuyiensis* as a highly supported clade (BS = 93, PP = 0.79) (Fig. 8).

IR/SC boundary comparison

The results show that the LSC/IRb boundary is located within the *rps19* gene and the IRa/LSC boundary within the *trnH* gene, a pattern that is consistent across all species examined (Fig. 9). Significant differences were observed in the distribution of the *ycf1* and *ndhF* genes at the IR/SC boundary among *Impatiens* species. In *I. huangyanensis*, the *ndhF* gene is entirely located within the SSC region, whereas in the other species examined, 16–17 bp of the

gene extend into the IRb region. The *ycf1* gene consistently spans the SSC/IRa boundary, but the length of the portion located within the SSC region varies among species. The plastome IR/SC boundary of *I. tainingensis* is similar to that of *I. platysepala* but differs in the lengths of the IR/SC regions and in the distribution length of the *ndhF* and *ycf1* genes at the boundary (Fig. 9).

Table 1. Comparison between *Impatiens tainingensis*, *I. platysepala*, *I. kuocangshanica*, and *I. huangyanensis* subsp. *Attenuate*.

Characters	<i>I. tainingensis</i>	<i>I. platysepala</i>	<i>I. kuocangshanica</i>	<i>I. huangyanensis</i> subsp. <i>attenuata</i>
Plant height	40–80 cm tall	30–50 cm tall	30–50 cm tall	20–40 cm tall
Leaves	petiole 2–4 cm long; leaves ovate-elliptic, 5–11 × 2–3.5 cm, lateral veins 5–7 pairs.	petiole 3–6 cm;leaves ovate-lanceolate, 8–15(-20) × 2.5–5 cm, with stipitate setose glands above middle, lateral veins 9–11 pairs.	petiole 2–6 cm; leaves ovate-elliptic, 5–8.5 × 2.5–4.5 cm, with pairs of stipitate glands, lateral veins 5–9 pairs.	petiole 1–3 cm; leaves ovate-elliptic, 2–6 × 1.5–4 cm, lateral veins 6–8 pairs.
Inflorescences	1–3-flowered; peduncles 1–2 cm. Pedicels 1.5–2.5 cm long; bracts 1–2 mm long, persistent, linear-lanceolate, apex shortly acute, green.	2- or 3-flowered; peduncles 1 cm. Pedicels 1.5–2.5 cm long; bracts 10–12 mm long, ovate-lanceolate, conspicuously cuspidate, pink.	2–4-flowered; peduncles 1 cm. Pedicels 1.5–2.2 cm long; bracts 7–8 mm long, persistent, linear-lanceolate, apex shortly acute, green.	1–3-flowered; peduncles 1 cm long; pedicels 1–2 cm long; bracts 3–4 mm long, persistent, green.
Lateral sepals	suborbicular, 6–8 × 5–8 mm, callous, apex green long mucronulate.	broadly ovate or suborbicular, 10–15 × 10–14 mm, 5-veined, apex shortly cuspidate.	ovate-orbicular, 8–10 × 6–8 mm, apex shortly cuspidate.	ovate rounded, 10–13 × 9–11 mm, apex cuspidate.
Lower sepal	purple striate, 1.9–2.4 cm deep, subsaccate-funnelform, gradually narrowed into an incurved spur; spur 1.5–1.8 cm long; mouth vertical, ca. 1.5–1.7 cm wide.	broadly funnelform, gradually narrowed into a curved or involute spur 3–4 cm; mouth vertical, ca. 2 cm wide, tip acuminate.	broadly funnelform, gradually narrowed into a curved or involute spur 3–4 cm; mouth vertical, ca. 2 cm wide, tip acuminate.	2.0 cm deep, saccate to widely saccate, attenuately constricted to a spur 2–3 cm; mouth vertical, 1.4–1.5 cm wide.
Upper petal	oblate, 1.2–1.3 × 1.7–1.9 cm	suborbicular, 1.6–1.8 cm in diam.	suborbicular, 1.2–1.5 cm in diam.	suborbicular, 1.3 × 1.3 cm
Lateral united petals	basal lobes 9–10 × 6–7 mm, apex obtuse; distal lobes 2.0–2.2 × 1.2–1.4 cm, apex obtuse or emarginate.	basal lobes oblong-obovate, 7–8 mm; distal lobes broadly dolabriform, 1.2–1.3 × 1–1.2 cm, apex obtuse.	basal lobes oblong-obovate, 7–8 mm; distal lobes broadly dolabriform, 1.2–1.3 × 1–1.2 cm, apex obtuse.	basal lobes obovate, 0.7–0.8 × 0.4–0.5 cm; distal lobes 1.7–2.0 × 0.6–0.9 cm
Capsule	fusiform, 1.5–2.0 cm long.	fusiform, 2.5–3.0 cm long.	linear-cylindric, 2.5–3.0 cm long.	linear-cylindric, 2.0–3.0 cm long.
Seeds	2.0 × 1.0 mm	3.0 × 2.0 mm	3.0 × 2.0 mm	2.89 × 1.77 mm

Taxonomic treatment

Impatiens tainingensis J.-D.Lin & P.Li, sp. nov.

urn:lsid:ipni.org:names:77375257-1

Figs 2, 3

Type. CHINA. Fujian • Taining County, Mt. Zhuangyuanyan, 26°58'12.35"N, 117°11'55.89"E, 312 m a.s.l., 31 Jul 2022, *Jin et al. Jin Xin Jie* 349 (holotype: ZM; isotype: HZU, FUN).

Diagnosis. *Impatiens tainingensis* is similar to *I. platysepala*, *I. kuocangshanica* and *I. huangyanensis* subsp. *attenuata* in pinkish purple flowers. But *I. tainingensis*

differs from *I. platysepala* by its bracts green, persistent, linear-lanceolate, 1–2 mm long; lower sepal subsaccate-funnelform, spur 1.5–1.8 cm long. *I. tainingensis* is distinct from *I. kuocangshanica* and *I. huangyanensis* subsp. *attenuata* in having lower sepal subsaccate-funnelform, spur 1.5–1.8 cm long; lateral sepals suborbicular, callous, 6–8 × 5–8 mm; capsules fusiform, 1.5–2.0 cm long and seeds 2.0 × 1.0 mm.

Description. Annual herb, 40–80 cm tall, glabrous. **Root** fibrous. **Stem** erect or ascending in lower part, slender and fleshy, simple, or laxly branched. **Leaves** alternate; petiole 2–4 cm long; blade papery, pale green, ovate-elliptic, 5–11 × 2–3.5 cm, lateral veins 5–7 pairs, curved, base cuneate, attenuate into petiole, margin crenate-serrate or crenate, teeth mucronulate, apex caudate-acuminate; **Inflorescences** axillary, 1–3-flowered; peduncles 1–2 cm long. Pedicels 1.5–2.5 cm long, bracteate at base; bracts persistent, linear-lanceolate, 1–2 mm long, apex shortly acute. **Flowers** pink-purple, ca. 3 cm deep. Lateral sepals 2, suborbicular, 6–8 × 5–8 mm, callous, margin entire, apex green long mucronulate, abaxial midvein narrowly carinate. Lower sepal purple striate, 1.9–2.4 cm deep, subsaccate-funnelform, gradually narrowed into an incurved spur; spur 1.5–1.8 cm long; mouth vertical, ca. 1.5–1.7 cm wide. Upper petal oblate, 1.2–1.3 × 1.7–1.9 cm, apex emarginate, shortly rostellate, abaxial midvein cristate; lateral united petals, shortly petiolate, 2-lobed; basal lobes obovate to dolabriform, small, 0.9–1.0 × 0.6–0.7 cm, apex obtuse; distal lobes dolabriform, large, 2.0–2.2 × 1.2–1.4 cm, apex obtuse or emarginate; auricle inflexed, yellow; Filaments linear, anthers ovoid, apex obtuse. Ovary erect, fusiform, ca.




Figure 2. Painted illustration of *Impatiens tainingensis*. (Drawn by Bo-Heng Li).




Figure 3. *Impatiens tainingensis*. **A.** Habitat; **B.** Whole plant; **C.** Flower, lateral view; **D.** Inflorescence; **E.** Flower, front view; **F.** Flower, lateral view; **G.** Flower structure and capsule. (Photos by Jie-Dong Lin).

5 mm long. **Capsule** fusiform or linear-cylindric, 1.5–2.0 cm long; seeds many, yellowish brown, ovoid-oblong, 2.0×1.0 mm, tuberculate.

Phenology. Flowering and fruiting from May to September.




Figure 4. Morphological comparison of *Impatiens tainingensis* (A–C), *I. kuocangshanica* (D–F), and *I. platysepala* (G–I). (Photos by Jun-Long Li).




Figure 5. Phylogenetic tree based on *atpB-rbcL* sequences. Numbers opposite nodes indicate bootstrap support percentages and posterior probabilities. An asterisk indicates a comb-like topology or species relationship incongruent with the maximum likelihood tree. *I. tainingensis* is shown in red.

Distribution and habitat. Taining, Fujian, southeastern China; known only from the type of location (Fig. 1). Moist places in valleys of Danxia landform; 300–400 m.

Conservation Status. Based on its limited area and extent of occurrence, *Impatiens tainingensis* could be categorized as near threatened (NT) according to IUCN criteria (IUCN Standards and Petitions Committee 2022). It is found at only three sites in Taining County in Fujian Province; there is no obvious downward trend in the population size, and there are currently thousands of individuals at each site.




Figure 6. Phylogenetic tree based on *trnL-F* sequences. Numbers opposite nodes indicate bootstrap support percentages and posterior probabilities. An asterisk indicates a comb-like topology or species relationship incongruent with the maximum likelihood tree. *I. tainingensis* is shown in red.




Figure 7. Phylogenetic tree based on complete plastid genome sequences. Numbers opposite nodes indicate bootstrap support percentages and posterior probabilities. An asterisk indicates a comb-like topology or species relationship incongruent with the maximum likelihood tree. *I. tainingensis* is shown in red.

Additional specimens examined (paratypes). CHINA. Fujian Province • Taining County, Mt. Zhuangyuanyan, 26°58'12.35"N, 117°11'55.89"E, 312 m, 9 August 2014 (fl.), *Jiedong Lin* Jin Xin Jie 397 (HZU).

Comparative material examined (allied species). *Impatiens chekiangensis* — CHINA. Fujian Province • Mt. Wuyi, 400 m, 22 October 1965 (fl.), *Guozong Mao* 10513 (HHBG). Zhejiang Province • Hangzhou City, Lin'an District, Changhua Town,

960 m, 19 June 1957 (fl. & fr.), *Deng et al.* 23509 (HHBG); • Shunxi Town, 280 m, 2 July 1986 (fl.), *Guojiang Zhang* L8442165 (IBSC); • Lishui City, Longquan City, 20 July 1958 (fl.), *Renye Sahn* 5510 (PE); *ibidem*, 14 September 1959 (fl.), *Shaoyao Zhang* 6799 (KUN); • Suichang County, Mt. Jiulong, 400 m, 22 September 1989 (fl.), *Yilin Chen* s.n. (PE); *ibidem*, 850 m, 5 July 1991, *Xu* 1115 (ZM); • Zhedaikou Town, Chenkeng Protection Station, 28°19'31"N, 118°49'43"E, 709.46 m, 29 October 2017 (fl. & fr.), *Xin Zhong et al.* ZX04178 (CSH); • Taizhou City, Xianju County, Yukeng Nature Reserve, 450 m, 20 July 2000 (fl.), *Xiaofeng Jin* 6918 (PE); • Wenzhou City, Yueqing City, Mt. Yandang, 250 m, 16 May 2005 (fl.), *Xiaofeng Jin & Peijian Cao* 1537 (PE); • Quzhou City, Wuxi River National Wetland Park, 26 April 2019 (fl. & fr.), *Yongfu Xu et al.* ZJQZWXJ20190426017 (CSFI); **Jiangxi** Province • Jiujiang City, Wuning County, Songxi Town, Yanxia Village, 29°23'13"N, 115°00'07"E, 145 m, 24 October 2013, *Xuanhuai Zhan et al.* LXP0609 (LBG).

Impatiens fujianensis — CHINA. **Fujian** Province • Wuyishan City, Sangu Town, Wuyi Mountain National Park, 27°44'56"N, 117°38'23"E, 1327 m, 4 October 2023 (fl.), *Liang Ma* 20231004001 (PE).

Impatiens huangyanensis — CHINA. **Zhejiang** Province • Taizhou City, Huangyan County, Shabu Town, Ersiheng Village, 300 m, 2 August 2000 (fl.), *Xiaofeng Jin* 6928 (PE); *ibidem*, 330 m, 2 August 2000 (fl.), *Xiaofeng Jin* 6929 (PE).

Impatiens kuocangshanica — CHINA. **Zhejiang** Province • Taizhou City, Xianju County, 15 May 1960 (fl.), 7887 (HHBG); • Yukeng Forest area, 350 m, 26 November 1982 (fl.), *Hangzhou Botanical Garden Herbarium* 2788 (HHBG).

Impatiens platysepala — CHINA • **Fujian** Province: fl. & fr., *H.C. Chao* 1788 (PE); 20 September 1932 (fl. & fr.), *Daxuan Wang* 838 (PE); • Chongan County, Mt. Wuyi, 380 m, 4 July 1974 (fl.), *Team* 236-6 499 (PE); • Nanping City, Songxi County, 27°26'43"N, 118°46'7"E, 675 m, 28 August 2017 (fl.), *Xiangxiu Su* CSH22213 (CSH). **Zhejiang** Province • Lishui City, Jingning County, 20 October 1964 (fl.), *Zongguo Mao* 10349 (HHBG); • Qingyuan County, Shangzhuang Village, 200 m, 21 September 1989 (fl.), *Yilin Chen* 89-02 (PE); • Wenzhou City, Taishun County, Chenmeikeng, 610 m, 5 May 1990 (fl.), *Li et al.* 0706 (ZM); • Quzhou City, Jiangshan City, Jianglang Mountain National Scenic Area, 28°31'57"N, 118°33'53"E, 25 April 2017 (fl.), *Xin zhong et al.* ZX03052 (CSH); • Taizhou City, Linhai County, Mt. Kuocangshan, 100 m, 2 July 2005 (fl.), *Xiaofeng Jin* 1551 (HTC). **Anhui** Province: • Lu'an City, Shucheng County, 500 m, 20 September 1996 (fl.), *M.B. Deng* 93034 (PE); • Huangshan City, Xiuning County, Mt. Qiyun, 480 m, 29°48'38"N, 118°1'33"E, 6 June 2012 (fl.), *D.E. Boufford et al.* 42916 (PE). **Jiangxi** Province • Shangrao City, Guangfeng District, 24 October 1958 (fl. & fr.), *Minxiang Nie & Shunshen Lai* 5930 (PE, KUN); • Wufushan Town, 1000 m, 14 September 1958 (fl.), *Shusheng Lai & Minxiang Nie* 5050 (IBSC, KUN); • Gangboshan Nature Reserve, 28°08'22"N, 118°16'42"E, 515 m, 14 June 2018 (fl.), *Zhenji Li et al.* AU02680 (AU); • Hengfeng County, Mt. Zheting, 60 m, 23 April 2013 (fl.), *Jianjun Zhou & Dasong Zhou* 20130424 (CSFI); • Qianshan County, Wangcun Village, 14 October 2017 (fl. & fr.), *Binjie Ge et al.* CSH21867 (CSH).

Impatiens platysepala* var. *chloroxantha — CHINA. **Fujian** Province • Mt. Wuyi, 27°38'20"N, 117°57'7"E, 243 m, 1 July 2019 (fl.), *Xiaohui Song* 2936 (AU); • 3 May 2015 (fl.), *Xiangxiu Su* CFH09011332 (CSH). **Zhejiang** Province • Lishui City, Suichang County, Mt. Jiulong, 600 m, 25 September 1989 (fl. & fr.), *Yilin Chen* 89-03 (PE); *ibidem*, 550 m, 21 August 1991, *Xu* 1234 (ZM); *ibidem*, 751.39 m, 5 June 2012 (fl.), *Qi Tian et al.* TQ01758 (CSH); • Hangzhou City, Lin'an District, Mt. Longtang, 850 m,




Figure 8. Phylogenetic tree based on ITS sequences. Numbers opposite nodes indicate bootstrap support percentages and posterior probabilities. An asterisk indicates a comb-like topology or species relationship incongruent with the maximum likelihood tree. *I. tainingensis* is shown in red.




Figure 9. Comparison of IR/SC boundaries among *Impatiens tainingensis* and related species. Positions of genes at the junctions between the large single-copy (LSC), small single-copy (SSC), and inverted repeat regions (IRa and IRb) are shown. Numbers above or within genes indicate lengths (bp) of gene fragments extending across the boundaries. Gene orientations are indicated by arrows. Total plastome sizes for each species are shown on the left.

27 June 1981 (fl.), *Chunsheng Xiang* 0020 (HTC); **Hubei** Province • Shennongjia National Park, QianjiaPing, 6 August 2010 (fl.), *Jinyu Li et al.* SN0079 (BJFC).

Impatiens wuyiensis — CHINA. **Fujian** Province • Wuyishan City, Yangzhuang Town, Longguiyuan Scenic Area, 27°51'07"N, 117°53'05"E, 519.9 m, 18 July 2021 (fl.), *Jingyi Wang* 136 (AU); *ibidem*, 27°51'10"N, 117°53'14"E, 527 m, 18 July 2021 (fl.), *Tao Wei* 993 (AU).

Key to *Impatiens tainingensis* and related species

- 1 Inflorescences subdivaricate, 2(or 3)-flowered; peduncles longer than pedicels.....***I. chekiangensis***
- Inflorescences subumbellate, 2- or 4-flowered; peduncles shorter than pedicels.....**2**
- 2 Bracts thinly membranous, pink, or yellow-green, ovate-lanceolate, 1–1.2 cm long.....***I. platysepala* (*I. platysepala* var. *chloroxantha*)**
- Bracts herbaceous, green, linear-lanceolate, shorter than 1 cm**3**
- 3 Flower Golden yellow; lateral sepals densely purple-red spotted ***I. wuyiensis***
- Flower pink-purple; lateral sepals not spotted**4**
- 4 Lower sepal subsaccate-funnelform, spur 1.5–1.8 cm long; lateral sepals suborbicular, callous, 6–8 × 5–8 mm..... ***I. tainingensis***
- Lower sepal broadly funnelform or saccate, spur 2–4 cm long; lateral sepals ovate-orbicular or ovate rounded, membranous, 8–10 × 6–8 mm or more**5**

- 5 Lower sepal broadly funnelform, gradually narrowed into a curved or involute spur 3–4 cm long ***I. kuocangshanica***
- Lower sepal saccate, base abruptly or gradually narrowed to a spur ca. 2 cm long ***I. huangyanensis* (*I. huangyanensis* subsp. *attenuata*)**

Discussion

Our integrative morphological and molecular evidence strongly supports the recognition of *Impatiens tainingensis* as an independent species. *Impatiens tainingensis* is distinguishable by a suite of stable morphological features, including notably smaller lateral sepals, a subsaccate-funnel-formed lower sepal, a short spur, and smaller capsules. These floral traits, together with leaf characters such as shorter petioles and fewer lateral veins, provide robust diagnostic characters for precise taxonomic delimitation. Although *I. tainingensis* is morphologically similar to *I. kuocangshanica* and *I. huangyanensis* subsp. *attenuata*, these taxa are phylogenetically distant. Phylogenetic analyses based on plastid and internal transcribed spacer (ITS) datasets consistently recovered *I. tainingensis* as a strongly supported monophyletic lineage. Despite *I. tainingensis* being phylogenetically close to *I. wuyiensis* and *I. platysepala* and its subspecific taxa, it differs from *I. platysepala* by its green, persistent, linear-lanceolate bracts (1–2 mm long). Furthermore, *I. platysepala* var. *chloroxantha* and *I. wuyiensis* are readily distinguished by their distinctive flower colors, yellow-green and golden-yellow, respectively. Incongruences between plastid and ITS phylogenetic trees may reflect incomplete lineage sorting, hybridization, or heterogeneous gene flow within *Impatiens* (Liang et al. 2025), including species related to *I. tainingensis*, which would be worthy of further investigation.

Comparative plastome analyses focusing on IR/SC boundaries provide additional structural evidence for the distinctiveness of *I. tainingensis*. Although its IR/SC junction is generally similar to that of *I. platysepala*, *I. tainingensis* exhibits differences in the lengths of IR and SC regions, as well as in the distribution patterns of the *ndhF* and *ycf1* genes across IR/SSC boundaries. Although these plastome variations alone are insufficient to define species boundaries, independent genome-structural characters—such as IR boundary shifts, repeat dynamics, and mutational hotspot divergence—when integrated with phylogenetic and morphological evidence, can provide complementary information and refine taxonomic resolution in morphologically complex groups (Luo et al. 2021; Qiu et al. 2023).

In summary, the integration of morphological distinctiveness, molecular phylogenetic evidence, and plastome structural variation provides strong support for the recognition of *Impatiens tainingensis* as a new species.

Acknowledgements

We sincerely thank Dr. Y.M. Yuan for manuscript revision and constructive suggestions and Jinhui Bao for providing seeds of *Impatiens tainingensis*. This research was supported by the National Natural Science Foundation of China (grant no. 32570239), the Science and Technology Projects of Xizang Autonomous Region, China (XZ202402ZD0005), Zhejiang Shuren University Research Start-up

Project (2024R055), and the China Conservation Collaboration initiative. We also acknowledge the Arnold Arboretum of Harvard University for sponsoring aspects of this research as part of the China Conservation Collaboration initiative.

Additional information

Conflict of interest

The authors have declared that no competing interests exist.

Ethical statement

No ethical statement was reported.

Use of AI

No use of AI was reported.

Funding

The National Natural Science Foundation of China (grant no. 32570239), the Science and Technology Projects of Xizang Autonomous Region, China (XZ202402ZD0005), Zhejiang Shuren University Research Start-up Project (2024R055) and the China Conservation Collaboration initiative, the Arnold Arboretum of Harvard University.

Author contributions

Investigation: XJ, JL. Supervision: PL. Visualization: BL, JL. Writing - original draft: MW, JL.

Author ORCIDs

Meizhen Wang  <https://orcid.org/0000-0002-3794-465X>

Jiedong Lin  <https://orcid.org/0000-0002-2966-1561>

Boheng Li  <https://orcid.org/0009-0005-8847-6883>

Junlong Li  <https://orcid.org/0009-0004-7694-032X>

Xinjie Jin  <https://orcid.org/0000-0003-3733-1957>

Pan Li  <https://orcid.org/0000-0002-9407-7740>

Data availability

All of the data that support the findings of this study are available in the main text or Supplementary Information.

References

- Amiryousefi A, Hyvönen J, Poczar P (2018) IRscope: An online program to visualize the junction sites of chloroplast genomes. *Bioinformatics* (Oxford, England) 34(17): 3030–3031. <https://doi.org/10.1093/bioinformatics/bty220>
- Chen YL (1988) A Revision of *Impatiens* L. from Chekiang – Studies on the Genus *Impatiens* L. in China (II). *Bulletin of Botanical Research* 8(2): 1–15. <https://archive.org/details/bulletin-botanical-research-harbin-8-001-016>
- Chen YL (1989) Four new species of *Impatiens* (Balsaminaceae) from China. *Acta Phytotaxonomica Sinica* 27(5): 395–404. <https://www.jse.ac.cn/EN/Y1989/V27/I5/395>
- Chen YL (1999) Six new species of *Impatiens* L. from China. *Zhiwu Fenlei Xuebao* 37(1): 88–99. <https://www.jse.ac.cn/EN/Y1999/V37/I1/88>

- Chen YL, Xu YL (1993) A new species of *Impatiens* (Balsaminaceae) from Zhejiang. *Bulletin of Botanical Research* 13(1): 11–13. https://bbr.nefu.edu.cn/CN/volumn/volumn_1254.shtml
- Chen YL, Akiyama S, Ohba H (2007) Balsaminaceae. In: Wu CY, Raven PH, Hong DY (Eds) *Flora of China*. Science Press, Beijing, and Missouri Botanical Garden Press, St. Louis, 43–355. <https://www.iplant.cn/info/Balsaminaceae?t=foc>
- Chen Y, Chen J, Yong QQ, Yuan TH, Wang Q, Li MJ, Long SW, Bai XX (2023) Species Diversity and Geographical Distribution Patterns of Balsaminaceae in China. *Diversity* 15: 1012. <https://doi.org/10.3390/d15091012>
- IUCN Standards and Petitions Committee (2022) Guidelines for using the IUCN red list categories and criteria, version 15. Prepared by the Standards and Petitions Committee. <https://www.iucnredlist.org/documents/RedListGuidelines.pdf> [Accessed 1 December 2023]
- Jin XF, Ding BY (2002) A new species of *Impatiens* from eastern Zhejiang, China. *Acta Phytotaxonomica Sinica* 40: 167–169. <https://archive.org/details/acta-phytotaxonomica-sinica-40-2-167-169>
- Jin XF, Yang SZ, Chen ZH, Qian L (2008) *Impatiens yilingiana* sp. nov. and *I. huangyanensis* subsp. *attenuata* subsp. nov. (Balsaminaceae) from Zhejiang, eastern China. *Nordic Journal of Botany* 26: 207–213. <https://doi.org/10.1111/j.1756-1051.2008.00325.x>
- Jin JJ, Yu WB, Yang JB, Song Y, dePamphilis CW, Yi TS, Li DZ (2020) GetOrganelle: A fast and versatile toolkit for accurate de novo assembly of organelle genomes. *Genome Biology* 21: 241. <https://doi.org/10.1186/s13059-020-02154-5>
- Kalyaanamoorthy S, Minh BQ, Wong TKF, Haeseler AV, Jermini LS (2017) ModelFinder: Fast model selection for accurate phylogenetic estimates. *Nature Methods* 14: 587–589. <https://doi.org/10.1038/nmeth.4285>
- Katoh K, Standley DM (2013) MAFFT multiple sequence alignment software version 7: Improvements in performance and usability. *Molecular Biology and Evolution* 30: 772–780. <https://doi.org/10.1093/molbev/mst010>
- Liang YF, Xue TT, Gadagkar SR, Qin F, Janssens SB, Yu SX (2025) Phylogenomic conflict analyses of plastid and mitochondrial genomes of *Impatiens* (Balsaminaceae) reveal its complex evolutionary history. *Molecular Phylogenetics and Evolution* 206: 108325. <https://doi.org/10.1016/j.ympev.2025.108325>
- Linné C, Salvius L (1753) *Species Plantarum*. Impensis Laurentii Salvii, Holmiae, 937. <https://doi.org/10.5962/bhl.title.669>
- Luo C, Huang WL, Sun HY, Yer H, Li XY, Li Y, Yan B, Wang Q, Wen YH, Huang MJ, Huang HQ (2021) Comparative chloroplast genome analysis of *Impatiens* species (Balsaminaceae) in the karst area of China: Insights into genome evolution and phylogenomic implications. *BMC Genomics* 22: 571. <https://doi.org/10.1186/s12864-021-07807-8>
- Minh BQ, Schmidt HA, Chernomor O, Schrempf D, Woodhams MD, von Haeseler A, Lanfear R (2020) IQ-TREE 2: New models and efficient methods for phylogenetic inference in the genomic era. *Molecular Biology and Evolution* 37: 1530–1534. <https://doi.org/10.1093/molbev/msaa015>
- Qiu H, Zhang ZH, Wang MZ, Jin XJ, Lin JD, Comes HP, Chen JX, Cui RN, Duan RQ, Li P (2023) Plastome evolution and phylogenomics of *Impatiens* (Balsaminaceae). *Planta* 257(2): 45. <https://doi.org/10.1007/s00425-023-04078-3>
- Ronquist F, Teslenko M, Mark van der P, Ayres DL, Darling A, Höhna S, Larget B, Liu L, Suchard MA, Huelsenbeck JP (2012) MRBAYES 3.2: Efficient Bayesian phylogenetic inference and model selection across a large model space. *Systematic Biology* 61: 539–542. <https://doi.org/10.1093/sysbio/sys029>

- Wight RA, Walker-Arnott G (1834) *Prodromus Florae Peninsulae Indiae Orientalis*: containing abridged descriptions of the plants found in the peninsula of British India, arranged according to the natural system: Vol. 1. *Prodromus Florae Peninsulae Indiae Orientalis*, London, 140. <https://doi.org/10.5962/bhl.title.252>
- Xu YL, Chen YL (1999) New taxa of *Impatiens* L. (Balsaminaceae) from Zhejiang, China. *Acta Phytotaxonomica Sinica* 37(2): 194–200. <https://www.jse.ac.cn/EN/Y1999/V37/I2/194>
- Yu SX (2012) *Balsaminaceae of China*. Peking University Press, Beijing. <https://www.las.ac.cn/front/book/detail?id=a8766a15110d895ce1c47aa6c4b060f3> [in Chinese]
- Yu SX, Janssens SB, Zhu XY, Liden M, Gao TG, Wang W (2016) Phylogeny of *Impatiens* (Balsaminaceae): Integrating molecular and morphological evidence into a new classification. *Cladistics: The International Journal of the Willi Hennig Society* 32(2): 179–197. <https://doi.org/10.1111/cla.12119>
- Yuan TH, Li MJ, Ren LY, Huang RX, Chen Y, Bai XX (2022) A dataset on the diversity and geographical distributions of wild *Impatiens* in China. *Biodiversity Science* 30: 22019. <https://doi.org/10.17520/biods.2022019>
- Zhang HW, Lu YF, Xu YL, Jin XF (2017) New materials of the seed plants in Zhejiang (V). *Journal of Hangzhou Normal University* 16(1): 32–35. [Natural Science Edition]

Supplementary material 1

GenBank accession numbers

Authors: Meizhen Wang, Jiedong Lin, Boheng Li, Junlong Li, Xinjie Jin, Pan Li

Data type: csv

Explanation note: Species and GenBank accession numbers for the sequences used in this study.

Copyright notice: This dataset is made available under the Open Database License (<http://opendatacommons.org/licenses/odbl/1.0/>). The Open Database License (ODbL) is a license agreement intended to allow users to freely share, modify, and use this Dataset while maintaining this same freedom for others, provided that the original source and author(s) are credited.

Link: <https://doi.org/10.3897/phytokeys.269.173115.suppl1>

Supplementary material 2

Collection information

Authors: Meizhen Wang, Jiedong Lin, Boheng Li, Junlong Li, Xinjie Jin, Pan Li

Data type: csv

Explanation note: Collection information for newly sequenced samples.

Copyright notice: This dataset is made available under the Open Database License (<http://opendatacommons.org/licenses/odbl/1.0/>). The Open Database License (ODbL) is a license agreement intended to allow users to freely share, modify, and use this Dataset while maintaining this same freedom for others, provided that the original source and author(s) are credited.

Link: <https://doi.org/10.3897/phytokeys.269.173115.suppl2>